

Date: Tuesday, 4/18/2006 1:05:24 PM
 User: Linda Lacelle

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : VALVE SEAL
Job Number : 26712	
Estimate Number : 12207	
P.O. Number : N/A	Part Number : D34707
This Issue : 4/18/2006 S.O. No. : N/A	Drawing Number : D3470 REV A
Prsht Rev. : NC	Project Number : N/A
First Issue : N/A Type : SMALL /MED FAB	Drawing Revision : A
Previous Run : 26266	Material : N/A
Written By : <u>SEE COMMENT BELOW</u>	Due Date : 4/25/2006 Qty: 10 Um: Each
Checked & Approved By : <u>CJOG104/18</u>	
Comment : Est Rev: A New Issue 06-02-06 JLM	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	MSIL60S125	high temp. silicone sheet .125
-----	------------	--------------------------------



Comment: Qty.: 0.0648 sf(s)/Unit Total : 0.6479 sf(s)

Material: ~~125~~ Thick High Temp Silicone sheet

(M-SIL60S.125)

Batch: B26173

SB 06/04/19 (10)

2.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
-----	-------------	-------------------------------



Comment: SMALL & MEDIUM FAB RESOURCE 1

1-Fabricate as per Dwg D3470

SB 06/04/19 (10)

3.0	QC5	INSPECT WORK TO CURRENT STEP
-----	-----	------------------------------



Comment: INSPECT WORK TO CURRENT STEP

BOC 04.24 (10)

4.0	PACKAGING 1	PACKAGING RESOURCE #1
-----	-------------	-----------------------



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: _____

BOC 04.27 (10)

5.0	DC	DOCUMENT CONTROL
-----	----	------------------



Comment: DOCUMENT CONTROL

Inspection Level 21

BOC 04.28 (10)

Job Completion



U 06.04.28

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector



Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☐ No ☒ DQA: ☒ Date: 06/04/28
 QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

DART

DESIGN <i>[Signature]</i>	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3470	REV. A SHEET 1 OF 4
DATE 05.12.14		TITLE SHUT-OFF VALVE SHAFT	SCALE 1:2
A	05.12.14	NEW ISSUE	

**D3470-041 SHUT-OFF VALVE SHAFT**

06.04.03 *[Signature]*

NOTES:

- 1) WELD PER DART QSI 004
- 2) FINISH: NONE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.010


QTY -041	P/N	DESCRIPTION
X	D3470-041	SHUT-OFF VALVE SHAFT
1	D3470-1	SHAFT
1	D3470-3	CONTROL ARM

COPYRIGHT © 2005 BY DART AEROSPACE LTD.


THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN <i>[Signature]</i>	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3470	REV. A SHEET 2 OF 4
DATE 05.12.14		TITLE SHUT-OFF VALVE SHAFT	SCALE 1:2

**D3470-1 SHAFT**

- 1) MATERIAL: AISI 303 STAINLESS STEEL 0.25 ROUND BAR
(REF. DART SPEC. M303R0.250)

**D3470-9 BOLT**
SCALE 1:1

- 1) MAKE FROM AN4-6 BOLT

NOTES:

- 2) FINISH: NONE
3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
4) ALL DIMENSIONS ARE IN INCHES
5) BREAK ALL SHARP EDGES 0.005 TO 0.010

COPYRIGHT © 2005 BY DART AEROSPACE LTD.


THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART


DESIGN <i>[Signature]</i>	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3470	REV. A SHEET 3 OF 4
DATE 05.12.14		TITLE SHUT-OFF VALVE SHAFT	SCALE 1:1

D3470-3 CONTROL ARM

- 1) MATERIAL: AISI 304/316 SS SHEET PER
MIL-S-5019 (ANNEALED) 2B
FINISH 13 GAUGE SS
(0.090 THICK)
(REF. DART SPEC. M304S13GA)

**D3470-5 BUTTERFLY VALVE**

- 1) MATERIAL: AISI 304/316 SS
SHEET PER
MIL-S-5019
(ANNEALED) 2B
FINISH 26 GAUGE
SS (0.018 THICK)
(REF. DART SPEC.
M304S26GA)

**NOTES:**


- 2) FINISH: NONE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.010

COPYRIGHT © 2005 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN <i>[Signature]</i>	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3470	REV. A SHEET 4 OF 4
DATE 05.12.14		TITLE SHUT-OFF VALVE SHAFT	SCALE 1:1

**D3470-7 BUTTERFLY VALVE SEAL****NOTES:**

- 1) MATERIAL: RED (OR GRAY) 60 DUROMETER HI-TEMPERATURE SILICONE SHEET, 0.063 THICK (REF. DART SPEC. M-SIL60-S.063)
- 2) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 3) ALL DIMENSIONS ARE IN INCHES
- 4) BREAK ALL SHARP EDGES 0.005 TO 0.010

COPYRIGHT © 2005 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.